



Attachment 3 to Item 2.1.2


Architectural Plans


Date of meeting: 19 October 2023 Location: By audio-visual link


Time: 10:00 a.m.





















SEE SHEET 1

Site Plan
This plan must not be read in isolation but in conjunction with reports contained within the development application it supports which include the following:

Statement of Environmental Effects
 Vegetation Management Plan

3) Farm Management Plan 4) Detail Survey Plan



Retaining Wall No.2 — SECTION

74.00

10.00

SCALE 1:250 HORIZONTAL. SCALE 1:250 VERTICAL.

ALTURA
SPATIAL
Registered Land and Engineering Surveyors
Surveying Australia's Future
P.O. Box 39, WINDSOR N.S.W. 2756
Ph. 0417 775171 or 0437 971232
email: mailbox@alturaspatial.com.au

top wall

Chainage

Level

Amendment No.	Date	0 10 20 30 40 50 Table o	of mm 100	110 120 130 140 15
Revision 7	07/01/22	Reduction Ratios	Prepared by :	MP
Revision 8 — no change on this plan	05/04/22	Plan : 1:250	Plan Date :	05/04/2022
		Horiz.: - Vert.:-	Checked :	GM
		Contour Interval :	Surveyed by :	MP+GM
		Datum : A.H.D.	Survey Date :	23/04/2021

Origin: SCIMS PM43998 RL99.919

Registered Surveyor <u>Gregory J Monaghan (ID.</u>1645)

Client :	Greenway Turf Supplies	Issue No :	SHEET No. 8 OF
Project :			10 SHEETS
,		File Ref : 1902	6-S1 Rev8.dwg
		Proj. Name :	
	being Lot 3 in D.P.548570	Plan Ref :	
	Proposed Retaining Walls 1 & 2 Sections	19026	6-S1

Notes for proposed Turf Farm

Proposed Nutrient Pond No.2

Nutrient pond construction is subject to approved design plans prepared in accordance with DCP Part D Chapter 6 Dam Construction after DA approval from Hawkesbury City Council.

Key design features to include:

- Stripping and stockpiling of all material and used in construction of the embankments and lining layer.
- The very stiff to hard clay material found below the ground surface is the material to be used for the clay blanket on the face of the wall, the core trench and the floor of the excavation. This clay shall be stockpiled and re-used once the excavation has been completed.
- A core trench
- The pond spillways are to be directed and shaped to match the current watercourse.

Access Track

The proposed access tracks will be constructed with all-weather gravel surfaces (possibly in road base crushed rock and/or recycled milled asphalt), materials to be sourced from on site where available and maintained to a standard where gravel contamination to the turf crop is minimised and be maintained to minimise dust by vehicles. This should ensure that material run-off during storm events is controlled.

The pavement of the accessway shall be sealed in order to suppress dust generation and the roadway to boundary zone shall be upgraded and maintained in accordance with Hawkesbury City Council "Driveway Specifications":

January 2016 in particular adopting the requirements of the Rural Vehicular Crossing standard drawings M57-3 & M57-4. Maintenance to these standards shall be carried out for the duration of the approved works

Catch Drains/Swales:

Drains are to be constructed of open channel and bunding. They are to channel all runoff from the farmed area into the proposed nutrient control ponds.

Riparian Corridor:

The watercourse area and the Vegetated Riparian Zone (VRZ) is to be detailed in a separate Landscape Plan (Vegetation Management Plan).

Screen Planting:

Perimeter planting of low lying native shrubs and ground cover is to be detailed in a separate Landscape Plan (Vegetation Management Plan).

Site regrading:

All paddocks shall be trimmed and excess material from the nutrient pond shall be used to level irregular areas over the remainder of the site regrading area.

The area marked on the plan as to be re-graded should include:

Refer to design by JWP "110636-02-DA001-DA102"

Stripping of top soil layer (approximated at 150mm) and stockpiled in appropriate locations as shown on the plan and specific detail shall be provided at Construction Certificate stage.

Earthworks cut and fill shall be carried out in accordance with HCC and EPA guidelines and specifications. Soil and sediment erosion controls to be in place prior to commencement of any works.

Erosion and Sediment Control

All erosion and sediment controls shall be in accordance with Managing Urban Stormwater: Soils and Construction ("Landcom Blue Book") (i.e. geotextile sediment fence and straw bales) shall be in place before any works are commenced. Erosion and sediment controls are to be adequately maintained at all times and must be installed in accordance with EPA guidelines. All controls shall remain in proper operation until all development activities have been completed and the site fully stabilised.

$\underline{\text{Construction/Installation of proposed gravity overflow drainage to Nutrient Pond No. 1.}\\$

Construction is to be carried out by a suitably experienced contractor. The surplus material is to be used as fill in the area requiring re-grading or in the proposed bunds no. 1 or 2.

Refer to design by JWP "110636-02-DA001-DA102"

General Notes for Dam Construction

(as per previously adopted Soil Conservation Service NSW design recommendations)

General

- 1. Dimensions shall not be obtained by scaling the drawings.
- 2. Set out dimensions shall be verified by the earthworks contractor.
- 3. Prior to the commencement of works the earthworks contractor shall locate all services in the area. Any damage to the existing services shall be rectified at the earthworks contractor's expense.
- Any underground services not referenced on the drawings may require specific protection works. The relevant authorities are to be contacted for instruction.
- 5. Workmanship and materials shall comply with the current Australian Standards.
- 6. All dimensions are in metres unless otherwise shown.

Construction Requirements for Dam Bank Embankments

(Extract from previously adopted dam design by Soil Conservation NSW)

- 1. All available topsoil shall be stripped from the new dam site. The topsoil is to be stripped before the construction of the dam embankment. The topsoil shall be re-used to cover the completed dam embankment down to 750mm below TWL. Any Excavation above TWL shall be covered with a minimum of 100mm of topsoil and then covered with Kikuyu Turf once excavation is completed.
- 2. All unsuitable material as observation during construction by the site supervisor shall be removed from beneath the location of the new dam embankment and used to fill the back batter of the dam wall.
- 3. Any stiff to hard clay material found below the ground surface is the material to be used for the clay blanket on the face of the wall, the core trench and the floor of the excavation. This clay shall be stockpiled out to the sides of the excavation, and re-used once the excavation has been completed and the plastic has been placed on the face of the wall. The clay material used for the clay blanket on the face of the wall & the floor of the excavation can be mixed with bentonite if required.
- 4. A core trench shall be excavated into suitable in-situ soil material for the length of the new dam wall to a minimum of 3m wide by 1m deep. This shall be verified on site by the earthworks supervisor before construction of the dam embankment.
- 5. Structural fill for the new dam embankments shall be placed in layers no greater than 150mm thick and be compacted to 98% Standard Maximum Dry Density at the optimum moisture content. To meet industry standards one compaction test should be done for every 200m³ of structural fill material placed in the dam embankment in accordance with AS 1289. A vibrating pad foot roller should be used.
- 6. A plastic liner shall be placed across the face of the wall. The Plastic liner shall be heavy duty builders plastic with a minimum thickness of 0.2mm. The Plastic liner shall extend from 1 metre above top water level down to the toe of the wall and out to the sides in the core trench of the dam wall a minimum of 1000mm deep. Consider clay bentonite mix material free of stones and rocks which can be placed back over the plastic liner in a 600mm layer to form the clay blanket across the face of the wall to finish with a 3(h):1(v) batter slope.
- 7. The outside batter of the dam embankment and crest of the dam embankment shall be covered with a minimum 100mm of topsoil on completion. The inside batter of the dam embankment shall be covered with topsoil 100mm thick to a minimum of 750mm below TWL.
- 8. Due to the low pH of the sub-soil 0.7kgs/m2 shall be spread on the finished surface of the dam embankment and any other areas of exposed sub-soil prior to the placement of topsoil.
- 9. On competition the topsoil shall be seeded with a pasture grass mixture suitable for the local area.

Dam Spillways:

- 1. All available topsoil shall be stripped from the site of the spillway to a depth of no less than 100mm for reuse in stabilisation works.
- 2. The earth spillway channel shall be a minimum of 3000mm wide and level along the contour. The outlet of the spillway shall be a minimum of 6000mm wide with 100mm of back slope on the channel.
- 3. The grassed slope below the sill shall be protected during construction of the dam embankment to ensure it is not disturbed by any machinery.

Dam Site Ground Water:

1. No dirty water can be discharged directly into any water course or drainage channel. Any discharge of water from site will need to meet EPA & Local council guide lines. The construction contractor will need to consult with the EPA and local council to determine their requirements in regards to discharge of water during construction prior to the commencement of works.

Other including Hawkesbury City Council (HCC) DCP Part D Chapter 6 Dam Construction requirements:

- 1. All earthwork areas including spillway are to be replanted or seeded with kikuyu grass.
- 2. A fenced area upstream and adjacent to the TWL is to be revegetated to filter water runoff...
- 3. Adhere to HCC rules regarding to Hydrological Aspects
- 4. Adhere to HCC rules regarding sediment control
- 5. Refer to HCC Chapter 6 Dam Construction for remaining construction requirements.
- 6. A work-as-executed plan shall be prepared upon completion of the works and shall include the location of the dam in relation to property boundaries.



Ph. 0417 775171 or 0437 971232

email: mailbox@alturaspatial.com.au

Amendment No.	Date	0 10 20
Revision 7	07/01/22	Reduction F
Revision 8 — no change on this plan	05/04/22	Plan : 1:N/A
		Horiz.: -
		Contour Interv
		Datum : A.H.
		

 O
 10
 20
 30
 40
 50
 Table of mm
 100
 110
 120
 130
 140
 150

 Reduction Ratios
 Prepared by: MP

 Plan Date:
 05/04/2022

 Checked:
 GM


 Contour Interval:
 Surveyed by: MP+GM


 Datum:
 A.H.D.


 Origin:
 SCIMS PM43998 RL99.919

 Registered Surveyor Gregory J Monaghan (ID.1645)

Client :	Greenway Turf Supplies	Issue No :	SHEET No. 9 OF
Project :			10 SHEETS
,	Site Plan of Proposed Turf Farm	File Ref : 19026	6-S1 Rev8.dwg
		Proj. Name :	
	being Lot 3 in D.P.548570	Plan Ref :	
	Construction Notes	19026	5-S1







LEVEL SPREADER (TYP.)

(FIGURE 3)

2. CATCH DRAIN PROFILES

Catch drains will be implemented to ensure that all runoff from the site is captured and directed to the nutrient control ponds. The catch drains have been sized for each catchment using the flow estimates derived from the XP-Rafts modelling and using Manning's calculations to determine the required configurations. The catch drains have been assumed to have a v-shaped profile with 1 in 4 batter slopes for ease of maintenance. A typical catch drain section is provided in Plate 2 below. The resulting profile configurations for each catchment are detailed in Table 3 below.




Plate 2 – Typical Section

Table 3 - Catch Drain Profiles


Catch Drain	20% AEP Flow (m³/s)	Required Depth (m)	Top Width (m)
Cat 1	0.13	0.23	1.84
Cat 2	0.25	0.29	2.32
Cat 3	0.49	0.37	2.96
Cat 4	0.18	0.26	2.08

Document: 110636-02-Nutrient Control Ponds - Stormwater Assessment.docx

3 of 4


CATCH DRAIN PROFILE AND SIZING

REFER TO REPORT BY J WYNDHAM PRINCE CONSULTING ENGINEERS 110636-02-Nutrient Control Ponds - Stormwater Assessment



TYPICAL CONCRETE BLOCK RETAINING WALL

NOT TO SCALE (FIGURE 4)



TYPICAL CONSTRUCTION ELEMENTS OF A DAM OR NUTRIENT POND

NOT TO SCALE

